

Sealed Quotations are invited for Following work up to 20 Dec 2020 at 3:00 pm.

| 1. RENOVATION OF PUNGHAT AND AROUND AREA | | | |
|---|---|------|------|
| TIME PERIOD: 45 days | | | |
| s.no | description of item | qty | unit |
| 1 | dismantling of existing tiles or flooring and relaying with new rustic tiles complete as per specification.(basic rate of tiles rs. 45/- per sqft) | 1100 | sqft |
| 2 | providing and fixing wall tiles including surface preparation complete as per specification.(basic rate of tiles rs. 45/- per sqft) | 200 | sqft |
| 3 | P&F factory made champered cc pavers 60mm thick m35 over 50mm sand including leveling of surface raising of chambers complete as per specification. | 600 | sqft |
| 4 | P&F 18 mm thick polished broda green marble on platforms complete as per specification. | 220 | sqft |
| 5 | making edge moulding and polishing complete as per specification. | 200 | rft |
| 6 | P&F granite 18mm thick complete as per specification. | 100 | sqft |
| 7 | P&F near ground level factory made kerbs stone m25 as per specification. | 80 | cft |
| 2. PAVER BLOCK FLOORING TO DAMAGED FLOOR IN FRONT OF BOTININACAL GARDEN | | | |
| TIME PERIOD: 45 days | | | |
| s.no | description of item | qty | unit |
| 1 | P&F factory made champered cc pavers 60mm thick m35 over 50mm sand including leveling of surface raising of chambers complete as per specification. | 4200 | sqft |
| 2 | P& L PCC 1:5:10 in foundation as per specification. | 10 | cum |
| 3 | Brick work with bricks of class designation of 75 in cement mortar 1:6 in foundation. | 2.6 | cum |
| 4 | P&F near ground level factory made kerbs stone m25 as per specification. | 5 | cum |
| 3. RELAYING OF DAMAGED FLOORING IN ROOM NO 5 OF F BLOCK HOSTEL | | | |
| TIME PERIOD: 15 DAYS | | | |
| s.no | description of item | qty | unit |
| 1 | Dismantling of marble flooring and relaying the marble flooring by using old marble pieces as per specification complete. | 160 | sqft |
| 2 | P& L PCC 1:5:10 in foundation as per specification. | 30 | cft |
| 3 | Flooring with marble tiles as per specification. | 50 | sqft |

As discussed in construction committee meeting dated 02/12/2020

Principal
MCM D.A.V. College for Women
Chandigarh

(MULTI L (MULTI L))


4. CONSTRUCTION OF NEW STORE & OPEN SHED IN SPORTS GROUND & STP

| TIME PERIOD: 45 days | | | |
|----------------------|---|-----|------|
| s.no | description of item | qty | unit |
| 1 | Brick work with bricks of class designation of 75 in cement mortar 1:6 in foundation. | 4 | CUM |
| 2 | P&L cement concrete flooring 50mm thick cc1:2:4 over 75mm thick cc1:5:10 complete | 40 | sqm |
| 3 | Making store by using old pannelling ,steel structure ,GI sheets,windows complete including fixing accesorios like screws nut bolts etc complete including carriage of material but excluding flooring. | 400 | sqft |
| 4 | Steel work in built up section for door frames and sheet doors including fixing,locking arrangement and primer,painting complete. | 300 | kg |
| 5 | P& L PCC 1:2:4 in foundation as per specification. | 1 | cum |
| 6 | P& L PCC 1:5:10 in foundation as per specification. | 1 | cum |
| 7 | earth work in excavation in foundation including refilling complete. | 3 | cum |
| 8 | Making open shed on STP by using old material such as steel structure GI sheets including carriage fixing complete in all respect. | 320 | sft |

5. RENOVATION OF PUNGHAT AND AROUND AREA

| TIME PERIOD: 60 days | | | |
|----------------------|---|-----|-------|
| s.no | description of item | qty | unit |
| 1 | dismantling of existing flooring and relaying with new tiles complete as per specification.(basic rate of tiles rs. 45/- per sqft) | 300 | sqft |
| 2 | providing and fixing wall tiles including surface prepration by dismantling complete as per specification.(basic rate of tiles rs. 45/- per sqft) | 750 | sqft |
| 3 | construction of rcc platform 50mm thick for counter wash basin and fixing granite on platform including edge moulding including cutting of granite for wash basin complete. | 30 | sqft |
| 4 | replacement of old WC with european WC with cistren including trap repair/replacement ,jet seat cover short body bib cock complete in all respect. | 2 | each |
| 5 | replacement of old WC with indian WC with cistren including trap repair/replacement ,short body bib cock complete in all respect. | 1 | each |
| 6 | P&F counter wash basin with pillar cock,angle valve , CP waste complete. | 2 | each |
| 7 | finishing walls with oil bound distemper,filling with putty including primer and prepration of surface. | 600 | sft |
| 8 | painting with synthetic enamel paint on old surface | 250 | sft |
| 9 | p&f ss toilet paper holder. | 3 | each |
| 10 | P&F looking glass 5mm thick with backing and studs complete 450x600mm. | 2 | each |
| 11 | Replacement of old damaged gi pipes 15 to 20 mm size with new complete including all fittings and fixtures. | 20 | meter |

As discussed in C.O. meeting
dt 02/12/2020


Principal
MCM D.A.V. College for Women
Chandigarh


ARTILAL MITTAL

GENERAL CONDITIONS AND SPECIFICATIONS

| | | | |
|---|---|--|--|
| 1 | The work shall be carried out as per CPWD specifications and as per instructions of Principal. | | |
| 2 | The work shall be completed in stipulated time period as mentioned in each work, otherwise 5% penalty will be imposed and deducted from their bill. | | |
| 3 | All material shall be used as specified. | | |
| 4 | Work shall be carried out in working hours of college. | | |
| 5 | Labour will not be allowed to stay in campus. | | |
| 6 | Electricity and water supply will be provided at one point for work only. | | |
| 7 | Any waste material or malba will have to be cleared at your own cost. | | |

MP
MOTI LAL MITTAL
 (CIVIL Engineer)

To be uploaded on website

*As discussed in meeting
 dt. 02/11/20*

MP
Principal
 MCM D.A.V. College for Women
 Chandigarh